



828-212-1378
support@shedsdirectinc.com
www.shedsdirectinc.com

Customer Responsibilities for Block Site Preparation

Proper site preparation is an important part of your investment in a building.

1. Block site preparation have become fairly common to the portable building industry. Years of history have shown that it is a successful way to support a building while keeping it off the ground.
2. Ideally your site should be no more than 8" off of level for the block site prep to be installed by your delivery driver.
3. 2" or 4" thick concrete blocks are placed on the ground starting on the uphill side of the building, then leveled from there. Blocks are placed approximately every 6' under every 4x4 runner. Shims and treated wedges are used where needed
4. The mule will usually be used to set your buildings on block. A 6' area on each end of the building is needed to maneuver the building.
5. It is very important that you, as the customer, knows where you want the building before the building is delivered. For example, marking the 4 corners will give you a a good idea f how the building will fit at your location. Keep in mind that you need a clear path for access, 2 ft wider than your building and 14ft high.
6. We have block site prep drawings available to purchase for \$195.

Any questions or concerns?

Please contact our scheduling department using the contact details below:

support@shedsdirectinc.com

828-212-1378

Site Preparation Building Diagram



To use the mule delivery, we need 6' of fairly level area on both ends of the building. (Exceptions can be made to this. Notes should be made on the order by the dealer, if these conditions cannot be met.)